



**पशुचिकित्सा एवं पशु विज्ञान महाविद्यालय, किशनगंज**  
**बिहार पशु विज्ञान विश्वविद्यालय**  
**College of Veterinary & Animal Sciences, Kishanganj**  
**BIHAR ANIMAL SCIENCES UNIVERSITY**



डॉ० चन्द्रहास  
अधिष्ठाता  
Dr. Chandrahas  
Dean

E-mail ID: deancov-basu-bih@gov.in  
deancovaskishanganj@gmail.com

L.No. 727/CVS,Kganj

Dated 08/10..../2025

**SHORT NOTICE INVITING QUOTATION**

From,  
The Dean  
College of Veterinary & Animal Sciences  
Kishanganj-855107

Sealed quotations are invited from the reputed firm/establishment/person for the following work to be done.

Name of the work –

1. Aluminium Partition work in Animal Experimental Laboratory, COVAS, Kishanganj vide file No.1152/CVS/Kganj/2025.

Designation of Officer		Dean, COVAS			
Place, Time & Date of receiving quotation		Dean office, COVAS, Kishanganj up to 14.10.2025 up to 3:00 p.m.			
Place, Time & Date of Opening Quotation		15.10.2025 in the Estate Office, COVAS, Kishanganj at 1:00 p.m.			
Sl No.	Description of Work	Quantity	Unit	Rate (incl. GST) (Rs.)	Amount (Rs.)
1.	Providing and fixing aluminium work partitions with all complete job.	48.79	Kg		
2.	Providing and fixing aluminium Frame of doors, windows, ventilators including complete Job	26	Kg		
3.	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. complete as per the directions of engineer-in-charge	3.186	Sqm		
4.	Providing and fixing 4 mm thick ACP partitions etc. complete as per the directions of engineer-in-charge	4.91	Sqm		
5.	Providing and fixing aluminium tubular handle bar 32 mm outer dia., 3.0 mm thick & 210 mm long with SS screws etc. complete as per direction of Engineer-in-Charge.	02	No.		
6.	providing and fixing bright finished 100 mm mortice lock with 6 levers without pair of handles of approved quality for aluminium door, with necessary screws etc complete as per direction of Engineer-in- charge.	01	No.		
Total Amount inclusive of all taxes and FOR:					

*Ch*  
08/10/2025



2. Aluminium Partition work in Dean Camp Office, COVAS, Kishanganj vide file No. 1226/CVS/Kganj/2025.

Sl No.	Description of Work	Quantity	Unit	Rate (incl. GST) (Rs.)	Amount (Rs.)
1.	Providing and fixing aluminium work partitions with all complete job.	42.4	Kg		
2.	Providing and fixing aluminium Frame of doors, windows, ventilators including complete Job	34.24	Kg		
3.	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. complete as per the directions of engineer-in-charge	2.946	Sqm		
4.	Providing and fixing 4 mm thick ACP partitions etc. complete as per the directions of engineer-in-charge	1.93	Sqm		
5.	Providing and fixing aluminium tubular handle bar 32 mm outer dia., 3.0 mm thick & 210 mm long with SS screws etc. complete as per direction of Engineer-in-Charge.	04	No.		
6.	providing and fixing bright finished 100 mm mortice lock with 6 levers without pair of handles of approved quality for aluminium door, with necessary screws etc complete as per direction of Engineer-in- charge.	01	No.		
7.	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer with necessary accessories and screws etc. complete.	02	No.		
8.	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC10 as per IS : 1868) transparent or dyed to required colour and shade with necessary screws etc. complete. (Single Rubber Stopper)	02	No.		
Total Amount inclusive of all taxes and FOR:					

*Ch*  
08/10/2025



3. Renovation (Aluminium Partition and Painting work in the Laboratory of Dept. of VGO, COVAS, Kishanganj vide file No. 1199/CVS/Kganj/2025.


Sl No.	Description of Work	Quantity	Unit	Rate (incl. GST) (Rs.)	Amount (Rs.)
1.	Providing and fixing aluminium work partitions with all complete job.	147.1136	Kg		
2.	Providing and fixing aluminium Frame of doors, windows, ventilators including complete Job	20.89	Kg		
3.	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. complete as per the directions of engineer-in-charge	10.625	Sqm		
4.	Providing and fixing 4 mm thick ACP partitions etc. complete as per the directions of engineer-in-charge	10.62	Sqm		
5.	Providing and fixing aluminium tubular handle bar 32 mm outer dia., 3.0 mm thick & 210 mm long with SS screws etc. complete as per direction of Engineer-in-Charge.	02	No.		
6.	providing and fixing bright finished 100 mm mortice lock with 6 levers without pair of handles of approved quality for aluminium door, with necessary screws etc complete as per direction of Engineer-in- charge.	01	No.		
7.	Removing white or colour wash by scrapping and sand paper in and preparing the surface smooth including necessary repair scratches etc. complete	21.30	Sqm		
8.	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	10.65	Sqm		
9.	Applying one coat of cement primer of approved brand and manufacture on wall surface:	21.30	Sqm		
10.	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade	21.30	Sqm		
11.	Providing and fixing 12.5 mm thick Gypsum plaster board	3.50	Sqm		
12.	Carpenter 1st Class for fixing Gypusm board	01	No.		
Total Amount inclusive of all taxes and FOR:					

*Ch*  
08/10/2025



**Terms and conditions:**

- (1) Paper to be submitted with quotation
  - i. GST Registration certificate
  - ii. PAN Number
  - iii. Civil Work Registration Certificate
- (2) Payment – 100% after satisfactory completion of work
- (3) Work to be completed within 20 days from the date of work order.
- (4) Name of work and Notice Letter No. should be mentioned on top of envelope.
- (5) Agency should inspect the site before filling in and submitting the quotation to get fully acquainted with the scope of work as no claim whatsoever will be entertained for any alleged ignorance thereof. Quotation must be submitted in original and without making any addition alternation, and as per given details given.
- (6) The sealed quotation can also be sent through courier/registered/speed post or in person. Conditional quotation or quotation received after due time and date shall not be entertained in any circumstances. University authority shall not be responsible for any delay or loss of the quotation document, the quotation will be open in the officer of the undersigned in presence of any intending quotationer or his/her authorized representative who may wish to be present at designated time and place.
- (7) Evaluation of bid will be done on the basis of total amount quoted by the quotationer/firm.
- (8) All disputes, what so ever shall be referred to the sole arbitration of the estate officer BASU, Patna and his decision shall be final and binding on the agency.
- (9) All the matters subject to the jurisdiction of Patna High Court.
- (10) The undersigned reserve the right to accept or reject any or all the quotation without assigning any reasons.
- (11) The contractor shall be responsible for the maintenance and defect liability of the completed civil work for a service period of 1 year from the date of completion.

  
Dean  
COVAS, Kishanganj

**Copy forwarded to:**

1. Secretary to the Vice-Chancellor, BASU, Patna for kind information.
2. Registrar, BASU, Patna for kind information.
3. Finance Comptroller BASU, Patna for kind information.
4. Director Work & Plant BASU, Patna for kind information.
5. Deputy Estate Officer, BASU, Patna.
6. COVAS, Notice Board.
7. Assistant Estate Officer Electrical BASU, Patna for kind information.
8. I/c ICT Cell, BASU, Patna to upload on website.